

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#A BREAKRM

1. General Details:

Floor Area **80.0** ft²
Avg. Ceiling Height **8.8** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **31.0** CFM
OA Requirement 2 **0.00** CFM/ft²
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **1.00** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.3. Electrical Equipment:

Wattage **0.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
S	59.0	0	0	0

3.1. Construction Types for Exposure S

Wall Type **Default Wall Assembly**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **80.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

7.1. 1st Partition Details:

(No partition data).

2.4. People:

Occupancy **4.0** People
Activity Level **Seated at Rest**
Sensible **230.0** BTU/hr/person
Latent **120.0** BTU/hr/person
Schedule **Sample Schedule**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

7.2. 2nd Partition Details:

Partition Type **Ceiling Partition**
Area **49.0** ft²
U-Value **0.030** BTU/(hr-ft²-°F)
Uncondit. Space Max Temp **85.0** °F
Ambient at Space Max Temp **95.0** °F
Uncondit. Space Min Temp **25.0** °F
Ambient at Space Min Temp **4.6** °F

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#A CORRIDOR

1. General Details:

Floor Area **49.0** ft²
Avg. Ceiling Height **8.8** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **4.0** CFM
OA Requirement 2 **0.0** CFM
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **0.50** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.3. Electrical Equipment:

Wattage **0.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
S	37.0	0	0	0

3.1. Construction Types for Exposure S

Wall Type **Default Wall Assembly**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **49.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

7.1. 1st Partition Details:

Partition Type **Wall Partition**
Area **37.0** ft²
U-Value **0.030** BTU/(hr-ft²-°F)
Uncondit. Space Max Temp **85.0** °F
Ambient at Space Max Temp **95.0** °F
Uncondit. Space Min Temp **25.0** °F
Ambient at Space Min Temp **4.6** °F

2.4. People:

Occupancy **0.0** Person
Activity Level **Seated at Rest**
Sensible **230.0** BTU/hr/person
Latent **120.0** BTU/hr/person
Schedule **Sample Schedule**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

7.2. 2nd Partition Details:

Partition Type **Ceiling Partition**
Area **49.0** ft²
U-Value **0.030** BTU/(hr-ft²-°F)
Uncondit. Space Max Temp **85.0** °F
Ambient at Space Max Temp **95.0** °F
Uncondit. Space Min Temp **25.0** °F
Ambient at Space Min Temp **4.6** °F

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#A ENTRANCE

1. General Details:

Floor Area **613.0** ft²
Avg. Ceiling Height **17.0** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **102.0** CFM
OA Requirement 2 **0.00** CFM/ft²
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **1.20** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.4. People:

Occupancy **9.0** People
Activity Level **Seated at Rest**
Sensible **230.0** BTU/hr/person
Latent **120.0** BTU/hr/person
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

2.3. Electrical Equipment:

Wattage **465.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
N	718.0	385	0	0
E	196.0	43	0	0

3.1. Construction Types for Exposure N

Wall Type **Default Wall Assembly**
1st Window Type **WINDOW**

3.2. Construction Types for Exposure E

Wall Type **Default Wall Assembly**
1st Window Type **WINDOW**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **549.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

7.1. 1st Partition Details:

Partition Type **Wall Partition**
Area **152.0** ft²
U-Value **0.030** BTU/(hr-ft²-°F)
Uncondit. Space Max Temp **85.0** °F
Ambient at Space Max Temp **95.0** °F
Uncondit. Space Min Temp **25.0** °F
Ambient at Space Min Temp **4.6** °F

7.2. 2nd Partition Details:

Partition Type **Ceiling Partition**
Area **549.0** ft²
U-Value **0.030** BTU/(hr-ft²-°F)
Uncondit. Space Max Temp **85.0** °F
Ambient at Space Max Temp **95.0** °F
Uncondit. Space Min Temp **25.0** °F
Ambient at Space Min Temp **4.6** °F

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#A OFF/CONF.

1. General Details:

Floor Area 272.0 ft²
Avg. Ceiling Height 7.8 ft
Building Weight 70.0 lb/ft²

1.1. OA Ventilation Requirements:

Space Usage User-Defined
OA Requirement 1 77.0 CFM
OA Requirement 2 0.00 CFM/ft²
Space Usage Defaults .. ASHRAE Standard 62.1-2007

2. Internals:

2.1. Overhead Lighting:

Fixture Type Recessed (Unvented)
Wattage 1.00 W/ft²
Ballast Multiplier 1.00
Schedule Sample Schedule

2.4. People:

Occupancy 9.0 People
Activity Level Seated at Rest
Sensible 230.0 BTU/hr/person
Latent 120.0 BTU/hr/person
Schedule Sample Schedule

2.2. Task Lighting:

Wattage 0.00 W/ft²
Schedule None

2.5. Miscellaneous Loads:

Sensible 0 BTU/hr
Schedule None
Latent 0 BTU/hr
Schedule None

2.3. Electrical Equipment:

Wattage 155.0 Watts
Schedule Sample Schedule

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
S	141.0	0	0	0
E	113.0	43	0	0

3.1. Construction Types for Exposure S

Wall Type Default Wall Assembly

3.2. Construction Types for Exposure E

Wall Type Default Wall Assembly
1st Window Type WINDOW

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling 0.00 CFM
Design Heating 0.00 CFM
Energy Analysis 0.00 CFM

Infiltration occurs only when the fan is off.

6. Floors:

Type Slab Floor On Grade
Floor Area 263.0 ft²
Total Floor U-Value 0.100 BTU/(hr-ft²-°F)
Exposed Perimeter 0.0 ft
Edge Insulation R-Value 0.00 (hr-ft²-°F)/BTU

7. Partitions:

7.1. 1st Partition Details:

Partition Type Wall Partition
Area 113.0 ft²
U-Value 0.030 BTU/(hr-ft²-°F)
Uncondit. Space Max Temp 85.0 °F
Ambient at Space Max Temp 95.0 °F
Uncondit. Space Min Temp 25.0 °F
Ambient at Space Min Temp 4.6 °F

7.2. 2nd Partition Details:

Partition Type Ceiling Partition
Area 272.0 ft²
U-Value 0.030 BTU/(hr-ft²-°F)
Uncondit. Space Max Temp 85.0 °F
Ambient at Space Max Temp 95.0 °F
Uncondit. Space Min Temp 25.0 °F
Ambient at Space Min Temp 4.6 °F

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#A WC

1. General Details:

Floor Area 45.0 ft²
Avg. Ceiling Height 10.0 ft
Building Weight 70.0 lb/ft²

1.1. OA Ventilation Requirements:

Space Usage User-Defined
OA Requirement 1 0.0 CFM/person
OA Requirement 2 0.00 CFM/ft²
Space Usage Defaults .. ASHRAE Standard 62.1-2007

2. Internals:

2.1. Overhead Lighting:

Fixture Type Recessed (Unvented)
Wattage 0.50 W/ft²
Ballast Multiplier 1.00
Schedule Sample Schedule

2.2. Task Lighting:

Wattage 0.00 W/ft²
Schedule None

2.3. Electrical Equipment:

Wattage 0.0 Watts
Schedule Sample Schedule

3. Walls, Windows, Doors:

(No Wall, Window, Door data).

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling 0.00 CFM
Design Heating 0.00 CFM
Energy Analysis 0.00 CFM

Infiltration occurs only when the fan is off.

6. Floors:

Type Slab Floor On Grade
Floor Area 45.0 ft²
Total Floor U-Value 0.100 BTU/(hr-ft²-°F)
Exposed Perimeter 0.0 ft
Edge Insulation R-Value 0.00 (hr-ft²-°F)/BTU

7. Partitions:

7.1. 1st Partition Details:

Partition Type Wall Partition
Area 66.0 ft²
U-Value 0.030 BTU/(hr-ft²-°F)
Uncondit. Space Max Temp 85.0 °F
Ambient at Space Max Temp 95.0 °F
Uncondit. Space Min Temp 25.0 °F
Ambient at Space Min Temp 4.6 °F

2.4. People:

Occupancy 1.0 Person
Activity Level Seated at Rest
Sensible 230.0 BTU/hr/person
Latent 120.0 BTU/hr/person
Schedule Sample Schedule

2.5. Miscellaneous Loads:

Sensible 0 BTU/hr
Schedule None
Latent 0 BTU/hr
Schedule None

7.2. 2nd Partition Details:

Partition Type Ceiling Partition
Area 45.0 ft²
U-Value 0.030 BTU/(hr-ft²-°F)
Uncondit. Space Max Temp 85.0 °F
Ambient at Space Max Temp 95.0 °F
Uncondit. Space Min Temp 25.0 °F
Ambient at Space Min Temp 4.6 °F

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#B

1. General Details:

Floor Area **460.0** ft²
Avg. Ceiling Height **17.0** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **91.0** CFM
OA Requirement 2 **0.0** CFM
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **1.20** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.3. Electrical Equipment:

Wattage **465.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
W	468.0	0	0	0
N	418.0	223	0	0
S	280.0	0	0	0

3.1. Construction Types for Exposure W

Wall Type **Default Wall Assembly**

3.2. Construction Types for Exposure N

Wall Type **Default Wall Assembly**
1st Window Type **WINDOW**

3.3. Construction Types for Exposure S

Wall Type **Default Wall Assembly**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **460.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

7.1. 1st Partition Details:

Partition Type **Wall Partition**
Area **165.0** ft²
U-Value **0.030** BTU/(hr-ft²-°F)
Uncondit. Space Max Temp **85.0** °F
Ambient at Space Max Temp **95.0** °F
Uncondit. Space Min Temp **25.0** °F

2.4. People:

Occupancy **9.0** People
Activity Level **Office Work**
Sensible **245.0** BTU/hr/person
Latent **205.0** BTU/hr/person
Schedule **Sample Schedule**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

Ambient at Space Min Temp **4.6** °F

7.2. 2nd Partition Details:

Partition Type	Ceiling Partition	Uncondit. Space Max Temp	85.0 °F
Area	538.0 ft²	Ambient at Space Max Temp	95.0 °F
U-Value	0.030 BTU/(hr-ft²-°F)	Uncondit. Space Min Temp	25.0 °F
		Ambient at Space Min Temp	4.6 °F

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#B WC

1. General Details:

Floor Area 45.0 ft²
Avg. Ceiling Height 10.0 ft
Building Weight 70.0 lb/ft²

1.1. OA Ventilation Requirements:

Space Usage User-Defined
OA Requirement 1 0.0 CFM/person
OA Requirement 2 0.00 CFM/ft²
Space Usage Defaults .. ASHRAE Standard 62.1-2007

2. Internals:

2.1. Overhead Lighting:

Fixture Type Recessed (Unvented)
Wattage 0.50 W/ft²
Ballast Multiplier 1.00
Schedule Sample Schedule

2.2. Task Lighting:

Wattage 0.00 W/ft²
Schedule None

2.3. Electrical Equipment:

Wattage 0.0 Watts
Schedule Sample Schedule

3. Walls, Windows, Doors:

(No Wall, Window, Door data).

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling 0.00 CFM
Design Heating 0.00 CFM
Energy Analysis 0.00 CFM

Infiltration occurs only when the fan is off.

6. Floors:

Type Slab Floor On Grade
Floor Area 45.0 ft²
Total Floor U-Value 0.100 BTU/(hr-ft²-°F)
Exposed Perimeter 0.0 ft
Edge Insulation R-Value 0.00 (hr-ft²-°F)/BTU

7. Partitions:

7.1. 1st Partition Details:

Partition Type Wall Partition
Area 66.0 ft²
U-Value 0.030 BTU/(hr-ft²-°F)
Uncondit. Space Max Temp 85.0 °F
Ambient at Space Max Temp 95.0 °F
Uncondit. Space Min Temp 25.0 °F
Ambient at Space Min Temp 4.6 °F

2.4. People:

Occupancy 1.0 Person
Activity Level Seated at Rest
Sensible 230.0 BTU/hr/person
Latent 120.0 BTU/hr/person
Schedule Sample Schedule

2.5. Miscellaneous Loads:

Sensible 0 BTU/hr
Schedule None
Latent 0 BTU/hr
Schedule None

7.2. 2nd Partition Details:

Partition Type Ceiling Partition
Area 45.0 ft²
U-Value 0.030 BTU/(hr-ft²-°F)
Uncondit. Space Max Temp 85.0 °F
Ambient at Space Max Temp 95.0 °F
Uncondit. Space Min Temp 25.0 °F
Ambient at Space Min Temp 4.6 °F

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#OFFICE-1

1. General Details:

Floor Area **95.0** ft²
Avg. Ceiling Height **8.8** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **26.0** CFM
OA Requirement 2 **0.0** CFM
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **1.00** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.3. Electrical Equipment:

Wattage **155.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
S	71.0	0	0	0

3.1. Construction Types for Exposure S

Wall Type **Default Wall Assembly**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **95.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

(No partition data).

2.4. People:

Occupancy **3.0** People
Activity Level **Seated at Rest**
Sensible **230.0** BTU/hr/person
Latent **120.0** BTU/hr/person
Schedule **Sample Schedule**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#OFFICE-2

1. General Details:

Floor Area **95.0** ft²
Avg. Ceiling Height **8.8** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **26.0** CFM
OA Requirement 2 **0.0** CFM
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **1.00** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.3. Electrical Equipment:

Wattage **155.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
S	71.0	0	0	0

3.1. Construction Types for Exposure S

Wall Type **Default Wall Assembly**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **95.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

(No partition data).

2.4. People:

Occupancy **3.0** People
Activity Level **Seated at Rest**
Sensible **230.0** BTU/hr/person
Latent **120.0** BTU/hr/person
Schedule **Sample Schedule**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#OFFICE-3

1. General Details:

Floor Area **95.0** ft²
Avg. Ceiling Height **8.8** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **26.0** CFM
OA Requirement 2 **0.0** CFM
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **1.00** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.4. People:

Occupancy **3.0** People
Activity Level **Seated at Rest**
Sensible **230.0** BTU/hr/person
Latent **120.0** BTU/hr/person
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

2.3. Electrical Equipment:

Wattage **155.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
S	71.0	0	0	0

3.1. Construction Types for Exposure S

Wall Type **Default Wall Assembly**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **95.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

(No partition data).

Space Input Data

STATE FARM , DENVER
M.Jawad

02/11/2023
03:24pm

TENANT SPACE#OFFICE-4

1. General Details:

Floor Area **95.0** ft²
Avg. Ceiling Height **8.8** ft
Building Weight **70.0** lb/ft²

1.1. OA Ventilation Requirements:

Space Usage **User-Defined**
OA Requirement 1 **26.0** CFM
OA Requirement 2 **0.0** CFM
Space Usage Defaults .. **ASHRAE Standard 62.1-2007**

2. Internals:

2.1. Overhead Lighting:

Fixture Type **Recessed (Unvented)**
Wattage **1.00** W/ft²
Ballast Multiplier **1.00**
Schedule **Sample Schedule**

2.4. People:

Occupancy **3.0** People
Activity Level **Seated at Rest**
Sensible **230.0** BTU/hr/person
Latent **120.0** BTU/hr/person
Schedule **Sample Schedule**

2.2. Task Lighting:

Wattage **0.00** W/ft²
Schedule **None**

2.5. Miscellaneous Loads:

Sensible **0** BTU/hr
Schedule **None**
Latent **0** BTU/hr
Schedule **None**

2.3. Electrical Equipment:

Wattage **155.0** Watts
Schedule **Sample Schedule**

3. Walls, Windows, Doors:

Exp.	Wall Gross Area (ft ²)	Window 1 Qty.	Window 2 Qty.	Door 1 Qty.
S	71.0	0	0	0
E	104.0	0	0	0

3.1. Construction Types for Exposure S

Wall Type **Default Wall Assembly**

3.2. Construction Types for Exposure E

Wall Type **Default Wall Assembly**

4. Roofs, Skylights:

(No Roof or Skylight data).

5. Infiltration:

Design Cooling **0.00** CFM
Design Heating **0.00** CFM
Energy Analysis **0.00** CFM
Infiltration occurs only when the fan is off.

6. Floors:

Type **Slab Floor On Grade**
Floor Area **95.0** ft²
Total Floor U-Value **0.100** BTU/(hr-ft²-°F)
Exposed Perimeter **0.0** ft
Edge Insulation R-Value **0.00** (hr-ft²-°F)/BTU

7. Partitions:

(No partition data).

Air System Sizing Summary for AHU-TENANT SPACE#A

Project Name: STATE FARM , DENVER
Prepared by: M.Jawad

02/11/2023
03:25pm

Air System Information

Air System Name AHU-TENANT SPACE#A
Equipment Class SPLT AHU
Air System Type SZCAV

Number of zones 1
Floor Area 1439.0 ft²
Location Denver, Colorado

Sizing Calculation Information

Calculation Months Jan to Dec
Sizing Data Calculated

Zone CFM Sizing Sum of space airflow rates
Space CFM Sizing Individual peak space loads

Central Cooling Coil Sizing Data

Total coil load 3.1 Tons
Total coil load 37.0 MBH
Sensible coil load 37.0 MBH
Coil CFM at Jul 1600 1910 CFM
Max block CFM 1910 CFM
Sum of peak zone CFM 1910 CFM
Sensible heat ratio 1.000
ft²/Ton 466.3
BTU/(hr-ft²) 25.7
Water flow @ 10.0 °F rise N/A

Load occurs at Jul 1600
OA DB / WB 92.2 / 59.8 °F
Entering DB / WB 78.9 / 59.4 °F
Leaving DB / WB 57.0 / 51.8 °F
Coil ADP 54.6 °F
Bypass Factor 0.100
Resulting RH 40 %
Design supply temp. 55.0 °F
Zone T-stat Check 1 of 1 OK
Max zone temperature deviation 0.0 °F

Central Heating Coil Sizing Data

Max coil load 36.1 MBH
Coil CFM at Des Htg 1910 CFM
Max coil CFM 1910 CFM
Water flow @ 20.0 °F drop N/A

Load occurs at Des Htg
BTU/(hr-ft²) 25.1
Ent. DB / Lvg DB 57.6 / 78.9 °F

Supply Fan Sizing Data

Actual max CFM 1910 CFM
Standard CFM 1570 CFM
Actual max CFM/ft² 1.33 CFM/ft²

Fan motor BHP 0.42 BHP
Fan motor kW 0.33 kW
Fan static 0.80 in wg

Outdoor Ventilation Air Data

Design airflow CFM 318 CFM
CFM/ft² 0.22 CFM/ft²

CFM/person 9.09 CFM/person

Zone Sizing Summary for AHU-TENANT SPACE#A

Project Name: STATE FARM , DENVER
Prepared by: M.Jawad

02/11/2023
03:25pm

Air System Information

Air System Name **AHU-TENANT SPACE#A**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **1439.0** ft²
Location **Denver, Colorado**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone CFM Sizing **Sum of space airflow rates**
Space CFM Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (MBH)	Design Airflow (CFM)	Minimum Airflow (CFM)	Time of Peak Load	Maximum Heating Load (MBH)	Zone Floor Area (ft²)	Zone CFM/ft²
Zone 1	32.7	1910	1910	Jun 1700	16.1	1439.0	1.33

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (MBH)	Time of Load	Air Flow (CFM)	Heating Load (MBH)	Floor Area (ft²)	Space CFM/ft²
Zone 1							
TENANT SPACE#A BREAKRM	1	1.2	Aug 1500	69	0.2	80.0	0.86
TENANT SPACE#A CORRIDOR	1	0.1	Aug 1500	10	0.2	49.0	0.20
TENANT SPACE#A ENTRANCE	1	19.2	Jun 1700	1082	12.5	613.0	1.76
TENANT SPACE#A OFF/CONF.	1	6.6	Jul 0900	374	2.1	272.0	1.38
TENANT SPACE#A WC	1	0.3	Jul 1500	18	0.2	45.0	0.41
TENANT SPACE#OFFICE-1	1	1.6	Aug 0300	89	0.2	95.0	0.93
TENANT SPACE#OFFICE-2	1	1.6	Aug 0300	89	0.2	95.0	0.93
TENANT SPACE#OFFICE-3	1	1.6	Aug 0300	89	0.2	95.0	0.93
TENANT SPACE#OFFICE-4	1	1.6	Aug 0200	91	0.4	95.0	0.96

Air System Sizing Summary for AHU-TENANT SPACE#B

Project Name: STATE FARM , DENVER
Prepared by: M.Jawad

02/11/2023
03:25pm

Air System Information

Air System Name **AHU-TENANT SPACE#B**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **505.0** ft²
Location **Denver, Colorado**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone CFM Sizing **Sum of space airflow rates**
Space CFM Sizing **Individual peak space loads**

Central Cooling Coil Sizing Data

Total coil load **1.2** Tons
Total coil load **13.9** MBH
Sensible coil load **13.9** MBH
Coil CFM at Jun 1700 **710** CFM
Max block CFM **710** CFM
Sum of peak zone CFM **710** CFM
Sensible heat ratio **1.000**
ft²/Ton **436.5**
BTU/(hr-ft²) **27.5**
Water flow @ 10.0 °F rise **N/A**

Load occurs at **Jun 1700**
OA DB / WB **87.3 / 57.1** °F
Entering DB / WB **77.7 / 60.4** °F
Leaving DB / WB **55.6 / 52.8** °F
Coil ADP **53.2** °F
Bypass Factor **0.100**
Resulting RH **45** %
Design supply temp. **55.0** °F
Zone T-stat Check **1 of 1** OK
Max zone temperature deviation **0.0** °F

Central Heating Coil Sizing Data

Max coil load **14.3** MBH
Coil CFM at Des Htg **710** CFM
Max coil CFM **710** CFM
Water flow @ 20.0 °F drop **N/A**

Load occurs at **Des Htg**
BTU/(hr-ft²) **28.2**
Ent. DB / Lvg DB **59.2 / 81.8** °F

Supply Fan Sizing Data

Actual max CFM **710** CFM
Standard CFM **583** CFM
Actual max CFM/ft² **1.41** CFM/ft²

Fan motor BHP **0.16** BHP
Fan motor kW **0.12** kW
Fan static **0.80** in wg

Outdoor Ventilation Air Data

Design airflow CFM **97** CFM
CFM/ft² **0.19** CFM/ft²

CFM/person **9.70** CFM/person

Zone Sizing Summary for AHU-TENANT SPACE#B

Project Name: STATE FARM , DENVER
Prepared by: M.Jawad

02/11/2023
03:25pm

Air System Information

Air System Name **AHU-TENANT SPACE#B**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **505.0** ft²
Location **Denver, Colorado**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone CFM Sizing **Sum of space airflow rates**
Space CFM Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (MBH)	Design Airflow (CFM)	Minimum Airflow (CFM)	Time of Peak Load	Maximum Heating Load (MBH)	Zone Floor Area (ft²)	Zone CFM/ft²
Zone 1	12.6	710	710	Jun 1700	8.8	505.0	1.41

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (MBH)	Time of Load	Air Flow (CFM)	Heating Load (MBH)	Floor Area (ft²)	Space CFM/ft²
Zone 1							
TENANT SPACE#B	1	12.3	Jun 1700	692	8.7	460.0	1.50
TENANT SPACE#B WC	1	0.3	Jul 1500	18	0.2	45.0	0.41